

Town of Mount Holly
PO Box 248
Mount Holly, VT 05758
(802) 259-2391
Fridays



OFFICE HOURS
8:30 a.m.–4:00 p.m.
Monday-Thursday
Closed
Closed

BID SPECIFICATION for FY23 Shim and Overlay Paving Village Area and Reclaiming Portion of Hortonville

1. Bid Name: FY23 Shim and Overlay Paving Village Area and Reclaiming Portion of Hortonville
2. Bid Deadline: August 31st, 2022, 3:30pm.
Bid must be in a sealed envelope marked “**BID ENCLOSED: FY23 Shim and Overlay Paving Village Area and Reclaiming Portion of Hortonville**” mailed or dropped off to:

Select Board
Town of Mount Holly
50 School Street
PO Box 248
Mount Holly, VT 05758

3. Bids will be opened and read at: Select Board Meeting of August 31st, 2022, 6:30pm
4. Specifications:

Location:

The Town of Mount Holly is seeking bids from qualified contractors to perform paving on:

Village Area – Belmont Road from Teer Rd to just south of Tarelville Rd intersection (library-used book shed), and Lake St in its entirety.

And to reclaim:

Portion of Hortonville Rd – from just north of Perry Road (under electric transmission line) to Shrewsbury Townline.

Village Area - Shim and Overlay

- Apply emulsion tack coat prior to install of shim and overlay asphalt.
- Install 1 ¼” shim/leveling course of Type IV Marshall Mix to correct road profile deficiencies and ¾” overlay of Type IV Marshall Mix – estimated 12,200 tons.
- All driveways to have a two-foot paved apron (paved driveways to be milled for smooth transition prior to overlay).
- Mill transitions for butt joints when tying into existing roads.



Portion of Hortonville Rd – Reclaim

- In place reclaim existing asphalt
 - Gradinof reclaim asphalt to be completed by town
5. Bond or Insurance Requirements: Bonding is not required. Insurance requirement will be per VTRANS 2018 Standard Specification Section 103.04.
6. Special Requirements:
- Provide pricing on attached Bid Proposal Form.
 - Eligibility: This procurement is open to those bidders who are prequalified by VTRANS for paving category.
 - 1st layer of asphalt placed should be compacted with rubber-tired roller.
 - Traffic control (signage and flaggers as necessary) will need to be provided by contractor; this will be incidental to the paving items. Contractor to coordinate with Road Foreman.
 - Emulsion/tack coat will be required between lift placements, this will be considered incidental to paving items.
 - Pavement markings will be completed by Town of Mount Holly.
 - Scope of work may vary based on bid results and funding available.
 - Quantities will be agreed upon at end of every day between contractor and road foreman. Quantities will be based on weight slips for ton priced unit items and field measurements for area priced unit items. Electronic copies of slips to be provided to town.
 - No advanced payments will be made. Work must be satisfactorily completed before being invoiced.
 - The town reserves the right to reject all bids and to either withdraw the bid request and reissue at a later time.
 - Bids will be evaluated per the Town of Mount Holly's Purchasing Policy (available online). Bids will be evaluated based on price, clarity and completeness of proposal, bidders' ability to perform work within specified time, bidders' experience and reputation, quality of materials, bidders' ability to meet other terms and conditions, including bonding and insurance requirement (if any), bidders' financial stability, and other factors that the Town determines are relevant.
 - Please email questions to Clinton Wooley at mthollyroads@vermontel.net.
QUESTIONS must be received by August 26th at 4:00pm.
 - Addendums if required will be posted to the town's website:
<http://www.mounthollyvt.org/announcements-bulletin-board/>.
7. Delivery Date: Project is anticipated to be awarded by August 31st, 2022. Paving needs to be completed prior to October 7th, 2022 and reclaim by October 21th, 2022.

Town of Mount Holly
 PO Box 248
 Mount Holly, VT 05758
 (802) 259-2391



OFFICE HOURS
 8:30 a.m.–4:00 p.m.
 Monday-Thursday
 Closed Fridays

BID PROPOSAL FORM – FY23 Shim and Overlay Paving Village Area and Reclaim Portion of Hortonville

This form must be completed by contractor, placed in sealed envelope marked with “FY23 Shim and Overlay Paving Village Area and Reclaim Portion of Hortonville” and submitted to Town Office at:

Select Board
 Town of Mount Holly
 50 School St
 PO Box 248
 Mount Holly, VT 05758)

Due: August 31, 2022 at 3:30pm

Acknowledgement of Addendum:

No. _____ Date: _____

No. _____ Date: _____

Description	Quantity	Unit	Unit Price (\$)	Extended Price (\$)
FY23 Shim and Overlay Paving Village Area and Reclaim Portion of Hortonville				
a. Type IV Shim and Overlay Asphalt	1220	tons		
b. Reclaim Asphalt	13500	sy		
			Total =	

Note: All prices shall be valid for 30 days from bid due date and for the duration of the contract period. Prices shall include all labor, equipment, and material costs. No adjustments will be made for fuel surcharges, delivery charges, and miscellaneous charges.

Contractor: _____

Address: _____

Phone: _____

Email: _____

Signature: _____ **Date:** _____